SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL								
REPORT REFERENCE	TITAN							
WEEKLY REFERENCE	9 2023							
SAMPLE	CEM I 52.5N							
SAND	FRENCH							
DATE OF RECEIPT OF SAMPLE	28-Feb-23							
DATE OF TESTS	28-Feb-23 to 28-Mar-23							
DATE OF REPORT	28-Mar-23							

ALL RESULTS ARE BASED ON THE SAMPLE RECEIVED FROM THE CLIENT							
FINENESS	4060 cm2/g (BSEN 196-6:2010)						
STANDARD CONSISTENCE	29.0 % (BSEN 196-3:2016)						
INITIAL SETTING TIME	181 mins (BSEN 196-3:2016)						

	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS		31.4	MPa	(Mean of 6 results,none discarded)
AT 7 DAYS		50.9	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS		64.2	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION: by mass, as received							
CHLORIDE	0.02	%	(BSEN 196-2:2013)				
AVERAGE CHLORIDE	0.02	Last 25 Results					
Na2O	0.21	%	(BSEN 196-2:2013)				
K2O	0.57	%	(BSEN 196-2:2013)				
Na2O (equiv)	0.59	%	(BSEN 196-2:2013)				
Na2O Average Alkali's	0.60 Last 25 Results						

END OF REPORT

SIGNED:......

Certificate signed by: / S.Burton A.M.I.C.1

S.Burton A.M.I.C.T Technical Manager J.M. Burton
Quality Manager