SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL						
REPORT REFERENCE	TITAN					
WEEKLY REFERENCE	28	2023				
SAMPLE	CEM I 52.5N					
SAND	FRENCH					
DATE OF RECEIPT OF SAMPLE	11-Jul-23					
DATE OF TESTS	11-Jul-23	to	8-Aug-23			
DATE OF REPORT	8-Aug-23					

ALL RESULTS ARE BASED ON THE SAMPLE RECEIVED FROM THE CLIENT					
FINENESS	3870 cm2/g	(BSEN 196-6:2010)			
STANDARD CONSISTENCE	30.0 %	(BSEN 196-3:2016)			
INITIAL SETTING TIME	179 mins	(BSEN 196-3:2016)			

COMPRESSIVE STRENGTH: MORT	COMPRESSIVE STRENGTH: MORTAR PRISMS		6-1:2016)
AT 2 DAYS	34.1	MPa	(Mean of 6 results,none discarded)
AT 7 DAYS	51.5	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	62.0	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION: by mass, as received					
CHLORIDE	0.01	%	(BSEN 196-2:2013)		
AVERAGE CHLORIDE	0.01	Last 25 Results			
Na2O	0.20	%	(BSEN 196-2:2013)		
К2О	0.63	%	(BSEN 196-2:2013)		
Na2O (equiv)	0.61	%	(BSEN 196-2:2013)		
Na2O Average Alkali's	0.58 Last 25 Results				

END OF REPORT

SIGNED:.....
Certificate signed by:

S.Burton A.M.I.C.T
Technical Manager

J.M. Burton
Quality Manager