KIRTON CONCRETE SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL						
REPORT REFERENCE	TITAN					
WEEKLY REFERENCE	11	2024				
SAMPLE	CEM I 52.5N					
SAND	FRENCH					
DATE OF RECEIPT OF SAMPLE	12-Mar-24					
DATE OF TESTS	12-Mar-24	to	9-Apr-24			
DATE OF REPORT	9-Apr-24					

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.					
FINENESS	3810 cm2/g	(BSEN 196-6:2010)			
STANDARD CONSISTENCE	30.0 %	(BSEN 196-3:2016)			
INITIAL SETTING TIME	185 mins	(BSEN 196-3:2016)			

	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS		30.9	MPa	(Mean of 6 results, none discarded)
AT 7 DAYS		46.4	MPa	(Mean of 6 results, none discarded)
AT 28 DAYS		60.8	MPa	(Mean of 6 results, none discarded)

CHEMICAL COMPOSITION: - by mass, as received						
CHLORIDE	0.04	%	(BSEN 196-2:2013)			
AVERAGE CHLORIDE	0.03	Last 25 Results				
Na2O	0.26	%	(BSEN 196-2:2013)			
К2О	0.54	%	(BSEN 196-2:2013)			
Na2O (equiv)	0.62	%	(BSEN 196-2:2013)			
Na2O Average Alkali's	0.59 Last 25 Results					

END OF REPORT

SIGNED:.....

Certificate signed by: / S.Burton A.M.I.C.T

S.Burton A.M.I.C.T
Technical Manager

J.M. Burton
Quality Manager