## SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL							
REPORT REFERENCE	TITAN						
WEEKLY REFERENCE	7 2025						
SAMPLE	CEM I 52.5N						
SAND	FRENCH						
DATE OF RECEIPT OF SAMPLE	20-Feb-25						
DATE OF TESTS	20-Feb-25 to 20-Mar-25						
DATE OF REPORT	20-Mar-25						

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.						
FINENESS	4380 cm2/g	(BSEN 196-6:2010 )				
STANDARD CONSISTENCE	30.0 %	(BSEN 196-3:2016)				
INITIAL SETTING TIME	203 mins	(BSEN 196-3:2016)				

COI	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS	36	5.7	MPa	(Mean of 6 results, none discarded)
AT 7 DAYS	50	).7	MPa	(Mean of 6 results, none discarded)
AT 28 DAYS	62	2.2	MPa	(Mean of 6 results, none discarded)

CHEMICAL COMPOSITION: - by mass, as received							
CHLORIDE	0.03	%	(BSEN 196-2:2013)				
AVERAGE CHLORIDE	0.05	Last 25 Results					
Na2O	0.25	%	(BSEN 196-2:2013)				
K2O	0.51	%	(BSEN 196-2:2013)				
Na2O (equiv)	0.59	%	(BSEN 196-2:2013)				
Na2O Average Alkali's	0.60 Last 25 Results						

## **END OF REPORT**

SIGNED:.....

Certificate signed by: S.Burton A.M.I.C.T

**Technical Manager** 

J.M. Burton
Quality Manager