SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL						
REPORT REFERENCE	TITAN					
WEEKLY REFERENCE	13	2025				
SAMPLE	CEM I 52.5N					
SAND	FRENCH					
DATE OF RECEIPT OF SAMPLE	1-Apr-25					
DATE OF TESTS	1-Apr-25	to	29-Apr-25			
DATE OF REPORT	29-Apr-25					

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.						
FINENESS	4090 cm2/g (BSEN 196-6:2010)					
STANDARD CONSISTENCE	29.5 % (BSEN 196-3:2016)					
INITIAL SETTING TIME	154 mins (BSEN 196-3:2016)					

COMPRESSIVE STRENGTH: MOR	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS	36.3	MPa	(Mean of 6 results, none discarded)	
AT 7 DAYS	53.4	MPa	(Mean of 6 results, none discarded)	
AT 28 DAYS	66.9	MPa	(Mean of 6 results, none discarded)	

CHEMICAL COMPOSITION: - by mass, as received					
CHLORIDE	0.02	%	(BSEN 196-2:2013)		
AVERAGE CHLORIDE	0.03	Last 25 Results			
Na2O	0.26	%	(BSEN 196-2:2013)		
К2О	0.46	%	(BSEN 196-2:2013)		
Na2O (equiv)	0.56	%	(BSEN 196-2:2013)		
Na2O Average Alkali's	0.56 Last 25 Results				

END OF REPORT

SIGNED:.....

Certificate signed by: / S.Burton A.M.I.C.T

Technical Manager

J.M. Burton
Quality Manager