## SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk

www.kirtonlab.co.uk





1175

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL							
REPORT REFERENCE	Titan 139						
CLIENT REFERENCE	CUBES 2025						
SHIP REFERENCE	"3-25						
SLUMP	ORDINARY PORTLAND CEMENT						
DATE OF RECEIPT OF SAMPLE	8-Apr-25						
DATE OF TESTS	8-Apr-25 to 6-May-25						
DATE OF REPORT	12-May-25						

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.								
COMPRESSIVE STRENGTH: Concrete Cubes								
AT 3 DAYS	33.9	35.5	35.1	Average	<b>34.8 MPa</b> BSEN 12390-2: 2019			
AT 7 DAYS	44.8	44.0	45.1	Average	<b>44.6</b> MPa BSEN 12390-2: 2019			
AT 28 DAYS	55.3	53.1	54.9	Average	<b>54.4</b> MPa BSEN 12390-2: 2019			

SLUMP	80	mm	
-------	----	----	--

Note:- The slump test was carried out on

14/04/2025

at

"11:10

as per BSEN 12350-2: 2019 by

S.Sykes A ten litre mixer was used for the the mixing of the sample, sampling was carried out in accordance with BSEN 12350-1: 2019. The slump cone was filled and the test carried out 2 mins +/- 30s from the end of mixing. The mixing, sampling and slump test were carried out at Kirton Concrete Services Ltd's. laboratory. The slump was a true slump.

## **END OF REPORT**



SIGNED:....

Certificate signed by:

S.Burton A.M.I.C.T

Fechnical Manager

**J.M. Burton**Quality Manager