KIRTON CONCRETE SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk

www.kirtonlab.co.uk





1175

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL								
REPORT REFERENCE	TITAN							
WEEKLY REFERENCE	28 2025							
SAMPLE	CEM I 52.5N							
SAND	FRENCH							
DATE OF RECEIPT OF SAMPLE	16-Jul-25							
DATE OF TESTS	16-Jul-25 to 13-Aug-25							
DATE OF REPORT	13-Aug-25							

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.						
FINENESS	3940 cm2/g (BSEN 196-6:2010)					
STANDARD CONSISTENCE	29.0 % (BSEN 196-3:2016)					
INITIAL SETTING TIME	194 mins (BSEN 196-3:2016)					

	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS		28.2	MPa	(Mean of 6 results, none discarded)
AT 7 DAYS		48.1	MPa	(Mean of 6 results, none discarded)
AT 28 DAYS		59.9	MPa	(Mean of 6 results, none discarded)

CHEMICAL COMPOSITION: - by mass, as received						
CHLORIDE	0.06	%	(BSEN 196-2:2013)			
AVERAGE CHLORIDE	0.06	Last 25 Results				
Na2O	0.29	%	(BSEN 196-2:2013)			
К2О	0.47	%	(BSEN 196-2:2013)			
Na2O (equiv)	0.60	%	(BSEN 196-2:2013)			
Na2O Average Alkali's	0.61 Last 25 Results					

END OF REPORT

SIGNED:.....

Certificate signed by:

S.Burton A.M.I.C.T

Technical Manager

J.M. Burton
Quality Manager