## KIRTON CONCRETE SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk

www.kirtonlab.co.uk





1175

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL							
REPORT REFERENCE	TITAN						
WEEKLY REFERENCE	29 2	2025					
SAMPLE	CEM I 52.5N						
SAND	FRENCH						
DATE OF RECEIPT OF SAMPLE	24-Jul-25						
DATE OF TESTS	24-Jul-25 t	:0	21-Aug-25				
DATE OF REPORT	21-Aug-25						

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.						
FINENESS	<b>4040 cm2/</b> g (B	SEN 196-6:2010 )				
STANDARD CONSISTENCE	<b>29.5</b> % (B	SEN 196-3:2016)				
INITIAL SETTING TIME	<b>206 mins</b> (B	SEN 196-3:2016)				

	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS		31.1	MPa	(Mean of 6 results, none discarded)
AT 7 DAYS		45.9	MPa	(Mean of 6 results, none discarded)
AT 28 DAYS		60.9	MPa	(Mean of 6 results, none discarded)

CHEMICAL COMPOSITION: by mass, as received						
CHLORIDE	0.05	%	(BSEN 196-2:2013)			
AVERAGE CHLORIDE	0.05	Last 25 Results				
Na2O	0.30	%	(BSEN 196-2:2013)			
К2О	0.53	%	(BSEN 196-2:2013)			
Na2O (equiv)	0.65	%	(BSEN 196-2:2013)			
Na2O Average Alkali's	0.66 Last 25 Results					

## **END OF REPORT**

SIGNED:.....

Certificate signed by: 

S.Burton A.M.I.C.T

**Technical Manager** 

J.M. Burton
Quality Manager