## SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL							
REPORT REFERENCE	TITAN						
WEEKLY REFERENCE	32 2025						
SAMPLE	CEM I 52.5N						
SAND	FRENCH						
DATE OF RECEIPT OF SAMPLE	12-Aug-25						
DATE OF TESTS	12-Aug-25 to 9-Sep-25						
DATE OF REPORT	9-Sep-25						

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.						
FINENESS	3940 cm2/g (BSEN 196-6:2010)					
STANDARD CONSISTENCE	29.0 % (BSEN 196-3:2016)					
INITIAL SETTING TIME	179 mins (BSEN 196-3:2016)					

	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS		29.6	MPa	(Mean of 6 results, none discarded)
AT 7 DAYS		46.0	MPa	(Mean of 6 results, none discarded)
AT 28 DAYS		59.1	MPa	(Mean of 6 results, none discarded)

CHEMICAL COMPOSITION: - by mass, as received							
CHLORIDE	0.05	%	(BSEN 196-2:2013)				
AVERAGE CHLORIDE	0.04	Last 25 Results					
Na2O	0.29	%	(BSEN 196-2:2013)				
K2O	0.47	%	(BSEN 196-2:2013)				
Na2O (equiv)	0.60	%	(BSEN 196-2:2013)				
Na2O Average Alkali's	0.59 Last 25 Results						

## **END OF REPORT**

SIGNED:.....
Certificate signed by: / S.Burton A.M.I.C.

S.Burton A.M.I.C.T
Technical Manager

**J.M. Burton**Quality Manager