KIRTON CONCRETE SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk

www.kirtonlab.co.uk





1175

An independent testing laboratory specialising in the testing of cementitious materials

PREPARED FOR TITAN CEMENT Ltd. HULL								
REPORT REFERENCE	TITAN							
WEEKLY REFERENCE	34 2025							
SAMPLE	CEM I 52.5N							
SAND	FRENCH							
DATE OF RECEIPT OF SAMPLE	27-Aug-25							
DATE OF TESTS	27-Aug-25 to 24-Sep-25							
DATE OF REPORT	24-Sep-25							

ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED.							
FINENESS	4000 cm2/g (BSEN 196-6:2010)						
STANDARD CONSISTENCE	29.0 % (BSEN 196-3:2016)						
INITIAL SETTING TIME	158 mins (BSEN 196-3:2016)						

	COMPRESSIVE STRENGTH: MORTAR PRISMS		(BSEN 196-1:2016)	
AT 2 DAYS		35.0	MPa	(Mean of 6 results, none discarded)
AT 7 DAYS		47.9	MPa	(Mean of 6 results, none discarded)
AT 28 DAYS		60.3	MPa	(Mean of 6 results, none discarded)

CHEMICAL COMPOSITION: by mass, as received							
CHLORIDE	0.03	%	(BSEN 196-2:2013)				
AVERAGE CHLORIDE	0.03	Last 25 Results					
Na2O	0.24	%	(BSEN 196-2:2013)				
К2О	0.50	%	(BSEN 196-2:2013)				
Na2O (equiv)	0.57	%	(BSEN 196-2:2013)				
Na2O Average Alkali's	0.57 Last 25 Results						

END OF REPORT

SIGNED:....

Certificate signed by:

S.Burton A.M.I.C.T

Technical Manager

J.M. Burton
Quality Manager