SERVICES LTD

Manor House, Station Road Hibaldstow DN20 9EB

T: 01652 656931 E: office@kirtonlab.co.uk





1175

www.kirtonlab.co.uk

An independent testing laboratory specialising in the testing of cementitious materials

| PREPARED FOR TITAN CEMENT Ltd. HULL | | | | | | |
|-------------------------------------|-------------|------|----------|--|--|--|
| REPORT REFERENCE | TITAN | | | | | |
| WEEKLY REFERENCE | 44 | 2025 | - | | | |
| SAMPLE | CEM I 52.5N | | | | | |
| SAND | FRENCH | | | | | |
| DATE OF RECEIPT OF SAMPLE | 4-Nov-25 | | | | | |
| DATE OF TESTS | 4-Nov-25 | to | 2-Dec-25 | | | |
| DATE OF REPORT | 2-Dec-25 | | | | | |

| ALL RESULTS ARE BASED ON SAMPLE RECEIVED FROM THE CLIENT: TESTED AS RECEIVED. | | | | | | |
|---|---------------------------------|--|--|--|--|--|
| FINENESS | 4040 cm2/g (BSEN 196-6:2010) | | | | | |
| STANDARD CONSISTENCE | 29.0 % (BSEN 196-3:2016) | | | | | |
| INITIAL SETTING TIME | 176 mins (BSEN 196-3:2016) | | | | | |

| | COMPRESSIVE STRENGTH: MORTAR PRISMS | | (BSEN 196-1:2016) | |
|------------|-------------------------------------|------|-------------------|-------------------------------------|
| AT 2 DAYS | | 35.2 | MPa | (Mean of 6 results, none discarded) |
| AT 7 DAYS | | 51.3 | MPa | (Mean of 6 results, none discarded) |
| AT 28 DAYS | | 66.3 | MPa | (Mean of 6 results, none discarded) |

| CHEMICAL COMPOSITION: - by mass, as received | | | | | | |
|--|----------------------|-----------------|-------------------|--|--|--|
| CHLORIDE | 0.03 | % | (BSEN 196-2:2013) | | | |
| AVERAGE CHLORIDE | 0.04 | Last 25 Results | | | | |
| Na2O | 0.25 | % | (BSEN 196-2:2013) | | | |
| K2O | 0.54 | % | (BSEN 196-2:2013) | | | |
| Na2O (equiv) | 0.61 | % | (BSEN 196-2:2013) | | | |
| Na2O Average Alkali's | 0.58 Last 25 Results | | | | | |

END OF REPORT

SIGNED:.....

Certificate signed by: / S.Burton A.M.I.C.

S.Burton A.M.I.C.T
Technical Manager

J.M. BurtonQuality Manager